Equipment: Hard Surface Cleaning Supplies > Pressure Washers > Electric Cabinet Stationary (Hot & Cold) Pressure Washers > Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump



Model Number: 5230SGF-15G3

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Manufacturer: Pressure Pro

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5 gpm 1500 psi 5 hp 230 volts 3 phase 15 amp General Pump

Specify either LP (liquid propane) or NG (natural gas) when ordering.

STANDARD FEATURES

Rugged powder coated steel frame, enclosed pump/motor compartment w/ hinged lid
Super efficient schedule 80 coil

Factory Installed
Pressure Pro PCA750-4 Replacement Burner Coil for 4-5 Gpm Pressure Washers

Stainless steel coil wrapper,

Factory Installed
Pressure Pro Stainless Coil Wrap PCA750-7 Fits Hot Shot Vertical 3.5-4.5 GPM Models

Control panel,
Float tank

Steambrite Supply

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Factory Installed
Pressure Pro Float Tank Assembly YFLOATTANK 1.05 gallons

Robert Shaw LP/NG electronic ignition 24 volt controls

Factory Installed
Robertshaw Natural Gas and Propane Valve

Commercial/Industrial grade motor

Factory Installed
Baldor Motor CEM3615T 5 Hp 3 Phase 3450 RPM 184T Frame 230 /460 Volts 6.7 Amps
or similar

Low speed V-belt driven General pump

Factory Installed
General Pump HTS2215S 5gpm 2300psi 1450rpm Emperor Run Dry High Temperature
or similar

High limit over temp protection

Steambrite Supply

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Factory Installed
225 Degree Switch Sensor 1/2" Mip with 3 Wire Leads

Controls water temperature.

Vacuum switch

Factory Installed
Mecline Vacuum Switch MVVS2.5

Used to control solenoids, Relays, and Low and No water safety switches.

Safety pressure relief valve

Factory Installed
Pressure Pro 22533A-4600 5000psi 3/8Mip 6 gpm 140 degree Pressure Relief Valve

Protects coil from over pressurization.

10′ power cord (no plug)

NOTE: All units are completely factory assembled, tested in the USA, and delivered ready to operate.

Steambrite Supply

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

STANDARD ACCESSORIES

Gun/wand assembly with insulated grip and quick connects

Factory Provided
Pressure Pro AGUD3621290C Washer Lance and Gun Combo 4060 psi Insulated Grip 36 in w Couplers

50′ high pressure hose w/quick connects

Factory Provided
Pressure Pro AHS330 Double Wire 50 ft Washer Hose 3/8 In 6000psi With Couplers Installed Black

Maxi-Flo 20% chemical injector assembly w/quick connects

Factory Provided
Pressure Pro ACI005 General Pump 100775 Maxi-Flow Fixed 20% Chemical Injector 3-5 gpm

4 color-coded QC spray nozzles

Factory Provided

Steambrite Supply

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Pressure Washing Nozzles, and Repair Parts

1 color-coded QC chemical soap injection nozzle

General pump Maintenance Guide

Owners Manual

Factory Warranty

Factory Brochure

Cleaning Units/Speed: 15,000
AVAILABLE OPTIONS

98-010 Panel Mount Thermostat $100

General Pump 100538 Dial Thermostat 86 - 250 Degrees F. 781999

Parts plus labor to be added

98-011 Hour Meter

Factory Installed
Digital Hour Meter 120 Volts, El 24-277 Ac/Dc 50/60 Hz - 8.749-316.0
Perfect for oil change intervals and other maintenance.

98-101 10Ë• Draft Diverter $185.83
98-102 Soap Solenoid w/ Panel Mount Switch $106.56

Steambrite Supply

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

98-104 Time-delay Shutdown w/ Adjustable Timer $308.00
98-105 Single Remote Station w/ Start/Stop/Burner $201.86
98-106 Multi Remote Stations w/ Start/Stop/Burner/Soap $344.82
98-107 Add’l Remote Stations $265.12
98-108 Oil Fired Option $238.69

Optional Factory installed
Beckett 240 Volt AFG Oil Burner 8.709-326.0 Pressure Pro301 VMG202

98-130 By-Pass Thermal Shutdown $89.66
98-510 18/5 Cable, Single Remote Station $1.16 per ft
98-512 18/7 Cable, Multi Remote Stations $1.39 per ft
Make your own pressure washing prespray

Make your own 55 gallon Drum of Concentrate Carpet Cleaner Tile Pressure Washing Prespray Cleaner

General Pump Oil

General Pump Oil Case 24 units
Required at first 50 hours and then every 200 hours

Descaler

Steambrite Supply

Equipment: Hard Surface Cleaning Supplies > Pressure Washers > Electric Cabinet Stationary (Hot & Cold) Pressure Washers > Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump

Shazaam: Descaler System Maintainer - 1 Gallon

Required every 100 hours of use.
1 gallon used at each descale service.
Prevents coil clogging and allows for less BTU of energy needed to heat the water.

All Stainless Steel Frame Models Available – consult sales rep

Options available for Pressure Pro Stationary HOT Washer 5230SGF-15G3 Natural Gas LP 5gpm 1500psi 5hp 230v 3ph 15amp General Pump :

Frame And Or Waste Tank Material

Stainless Steel Frame (stainless tank included), Powder Coat Steel.

Extended Warranty

+ No Extended Warranty, 2 Additional Years Parts Plus On Site Labor (Items under $5000.00) [SBMW2-5000], 4 Additional Years Parts Plus On Site Labor (Items under $5000.00) [SBMW4-5000].

Shipping Surcharges

None Commercial Address Forklift / Loading Dock On Site No Appointment Provided, Commercial Address But Needs Liftgate Service Because No Forklift or Dock on Site No Appointment Provided, Home Delivery Needs Liftgate Curb Service Because No Forklift On Site (Required) No Appointment Provided.

Hour Meter-Panel Mount (120v)

+ None, Factory or Dealer Installed.

Fuel Used

Propane (LP) Extra 30 Day Wait Required, Natural Gas (NG).

Availability: This product was added to our catalog on Sunday 25 January, 2015