Equipment: Hard Surface Cleaning Supplies > Pressure Washers > Electric Cabinet Stationary (Hot & Cold) Pressure Washers > Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump



Model Number: 8230SGF-30G3

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Manufacturer: Pressure Pro

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8 gpm 3000 psi 15 hp 230 volts 3 phase 39 amp General Pump
Dual (2) Gun capable!

Specify either LP (liquid propane) or NG (natural gas) when ordering.

STANDARD FEATURES

Rugged powder coated steel frame, enclosed pump/motor compartment w/ hinged lid
Super efficient schedule 80 coil

Factory Installed
Pressure Pro PCA750-12 Replacement Burner Coil for 5-6 Gpm Pressure Washers
or similar

Stainless steel coil wrapper,

Factory Installed
Pressure Pro Stainless Coil Wrap PCA750-13 Fits Hot Shot Vertical 5-6 GPM Models
or similar

Control panel,
Float tank

Steambrite Supply

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Factory Installed
Pressure Pro Float Tank Assembly YFLOATTANK 1.05 gallons

Robert Shaw LP/NG electronic ignition 24 volt controls

Factory Installed
Robertshaw Natural Gas and Propane Valve

Commercial/Industrial grade motor

Factory Installed
Baldor Motor EM3713T 15 Hp 3 Phase 3450 RPM 215T Frame 208-230/460 Volts 17 Amps
or similar

Low speed V-belt driven General Pump

Factory Installed
General Pump TSF2021 Pressure Washing Carpet Cleaning Pump 3600psi 1750rpm (TSF-2021) 8.5 gpm 8.702-740.0
or similar

Steambrite Supply

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

High limit over temp protection

Factory Installed
225 Degree Switch Sensor 1/2" Mip with 3 Wire Leads

Controls water temperature.

Vacuum switch

Factory Installed
Mecline Vacuum Switch MVVS2.5

Used to control solenoids, Relays, and Low and No water safety switches.

Safety pressure relief valve

Factory Installed
Pressure Pro 22533A-4600 5000psi 3/8Mip 6 gpm 140 degree Pressure Relief Valve

Protects coil from over pressurization.

10′ power cord (no plug)

Steambrite Supply

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

NOTE: All units are completely factory assembled, tested in the USA, and delivered ready to operate.

STANDARD ACCESSORIES

Gun/wand assembly with insulated grip and quick connects

Factory Provided
Pressure Pro AGUD3621290C Washer Lance and Gun Combo 4060 psi Insulated Grip 36 in w Couplers

50′ high pressure hose w/quick connects

Factory Provided
Pressure Pro AHS330 Double Wire 50 ft Washer Hose 3/8 In 6000psi With Couplers Installed Black

Maxi-Flo 20% chemical injector assembly w/quick connects

Factory Provided
Pressure Pro ACI005 General Pump 100775 Maxi-Flow Fixed 20% Chemical Injector 3-5 gpm

4 color-coded QC spray nozzles

Steambrite Supply

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Factory Provided
Pressure Washing Nozzles, and Repair Parts

1 color-coded QC chemical soap injection nozzle

General pump Maintenance Guide

Owners Manual

Factory Warranty

Factory Brochure

Cleaning Units/Speed: 48,000
AVAILABLE OPTIONS

98-010 Panel Mount Thermostat $100

General Pump 100538 Dial Thermostat 86 - 250 Degrees F. 781999

Parts plus labor to be added

98-011 Hour Meter

Factory Installed
Digital Hour Meter 120 Volts, El 24-277 Ac/Dc 50/60 Hz - 8.749-316.0
Perfect for oil change and descale intervals and other maintenance.

Steambrite Supply

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

98-101 10Ë• Draft Diverter $185.83
98-102 Soap Solenoid w/ Panel Mount Switch $106.56
98-104 Time-delay Shutdown w/ Adjustable Timer $308.00
98-105 Single Remote Station w/ Start/Stop/Burner $201.86
98-106 Multi Remote Stations w/ Start/Stop/Burner/Soap $344.82
98-107 Add’l Remote Stations $265.12
98-108 Oil Fired Option $238.69

Optional Factory installed
Beckett 240 Volt AFG Oil Burner 8.709-326.0 Pressure Pro301 VMG202

98-130 By-Pass Thermal Shutdown $89.66
98-510 18/5 Cable, Single Remote Station $1.16 per ft
98-512 18/7 Cable, Multi Remote Stations $1.39 per ft
Make your own pressure washing prespray

Make your own 55 gallon Drum of Concentrate Carpet Cleaner Tile Pressure Washing Prespray Cleaner

This will become your favorite cleaner!

General Pump Oil

General Pump Oil Case 24 units
Required at 50 hours and then every 200 hours

Steambrite Supply

Equipment: Hard Surface Cleaning Supplies > Pressure Washers > Electric Cabinet Stationary (Hot & Cold) Pressure Washers > Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump

Descaler

Shazaam: Descaler System Maintainer - 1 Gallon

Required every 100 hours of use.
One gallon is used for each descale job.
Prevent coil mineral clogging and allows equipment to consume less BTU's of fuel to heat the water.

All Stainless Steel Frame Models Available – Consult sales rep. Raw Stainless prices subject to change without notice.

Options available for Pressure Pro Stationary HOT Washer 8230SGF-30G3 Natural Gas LP 8gpm 3000psi 15hp 230v 3ph 39amp General Pump :

Frame And Or Waste Tank Material

Stainless Steel Frame (stainless tank included), Powder Coat Steel.

Extended Warranty

+ No Extended Warranty, 2 Additional Years Parts Plus On Site Labor (Items under $7500.00) [SBMW2-7500], 4 Additional Years Parts Plus On Site Labor (Items under $7500.00) [SBMW4-7500].

Shipping Surcharges

None Commercial Address Forklift / Loading Dock On Site No Appointment Provided, Commercial Address But Needs Liftgate Service Because No Forklift or Dock on Site No Appointment Provided.

Hour Meter-Panel Mount (120v)

+ None, Factory or Dealer Installed.

Fuel Used

Propane (LP) Extra 30 Day Wait Required, Natural Gas (NG).

Availability: This product was added to our catalog on Monday 26 January, 2015